



# नगर कार्यपालिकाको कार्यालय

## Office of the Municipal Executive

(Google Plus Code: C8RJ+C6 Neulapur)

सैनवार, बर्दिया

Sainawar, Bardiy

लुम्बिनी प्रदेश, नेपाल

Lumbini Province, Nepal

**विषय: दरभाउपत्र पेश गर्ने सम्बन्धि सार्वजनिक सूचना !!**

**(सूचना प्रकासन मिति: २०८३/०२/२२)**

प्रस्तुत विषयमा यस पालिका हाताभित्र पर्यापर्यटन सूचना केन्द्र तथा कृषि जैविक विविधता अभिलेखालय निर्माण गर्नुपर्ने भएकोले उक्त कार्यको स्वीकृत लागत अनुमान रु.७,९९,९७८.३(मु.अ.क.सहित) भित्र रही कार्यालयबाट उपलब्ध गराइएको BOQ बमोजिम उक्त भवन निर्माण कार्य गर्न ईच्छुक निर्माण ब्यवसायी तथा फर्महरुबाट यो सूचना प्रकाशित भएको मिति देखि ५ औं दिन (मिति २०८३/०२/२६) कार्यालय समय भित्र के/कति दरमा गर्न सकिने हो ? दरभाउपत्र र तपसिल बमोजिमको कागजातसहित पेश गर्नु हुन जानकारी गराइन्छ।

**तपसिल:**

- १) फर्म दर्ता प्रतिलिपि
- २) स्थाई लेखा नम्बर/दर्ता प्रमाणको प्रतिलिपि
- ३) आ. ब. २०८१/८२ को कर चुत्ता प्रमाणपत्रको प्रतिलिपि
- ४) रु. १०००।० तिरेको राजश्व

मंगल बहादुर शाही  
प्रमुख प्रशासकीय अधिकृत

"समुन्नत ठाकुरबाबा: सबल नगरवासी"

वेबसाइट: www.thakurbabamun.gov.np ईमेल: thakurbabamun@gmail.com

मंगल बहादुर शाही  
प्रमुख प्रशासकीय अधिकृत

Thakurbaba Municipality  
Office of Municipal Executive  
Sainawar Bardiya

Project Name :- Jaibhik Krishi Abhilekhalaya Bhawan  
Location :- Thakurbaba-4, Bardiya  
Type of Work :- Timber Structure  
Estimated Work Completion Date :

F/Y: 2082/83

BOQ

SN.	Description	Unit	Quantity	Rate (Rs)		Amount ( NRs)	Remarks
				In Figure	In Words		
<b>A. General Work</b>							
1	Supply and erection of Project Information board 0.9 m x 1.2 m size including full compensation for labour,materials,transoprtation and other incidental all complete as per Instruction of site Engineer.	PS	1.00	3000.00	Three Thousand Rupees Only	3000.00	
<b>Total General Cost (A)</b>						<b>3000.00</b>	
<b>B. Construction Works</b>							
1	Earthwork excavation in all Soft/Medium soils for building foundation and site development by Manually, lift up to 1.5m ramming of bottom , stacking of excavated materials at 10m, clear from the edge of foundation trench, all complete as per specification, drawings and instruction of site engineer.	CUM	4.99				
2	Filling with approved soil (transported soil from outside) in to the flooring of building/structure/ground. Back filling materials shall be applied on layers by layers of 150 mm thick, watering and compaction and all complete as per specification,drawings and instruction of Site Engineer.	CUM	14.98				
3	Supplying And Laying Of Dry Brick Flooring in perfect line and level with Sand including Ground Compaction and the cost of all materials and other accessories etc all complete as per specification, drawings and Instruction of Site Engineer	SQM	27.10				
4	Providing, laying, compacting and curing plain cement concrete M15 (1:2:4) with OPC cement 43 grade Minimum, crusher washed sand and crushed aggregate(using mixture machine) finishing to approved level, lines and dimensions using vibrator and all complete as per drawings, specifications and as per Instruction of Site Engineer.	CUM	4.86				
5	Providing, laying, compacting and curing plain cement concrete M20 (1:1.5:3) with OPC cement 43 grade Minimum, crusher washed sand and crushed aggregate water proof chemical agent and admixture in Top Of Slab (using mixture machine) finishing to approved level, lines and dimensions using vibrator and all complete as per drawings, specifications and as per Instruction of Site Engineer.	CUM	1.35				

Thakurbaba नगरपालिका  
निकासाधिकारी कार्यालय  
सुनवार, बर्दिया  
लुम्बिनी प्रदेश नेपाल  
स्था. २०७३

मंगल शही  
प्रमुख प्रशासकीय अधिकृत

BOQ							
Sl. No.	Description	Unit	Quantity	Rate (Rs)		Amount (NRs)	Remarks
				In Figure	In Words		
6	Formworks: Providing 12mm thick waterproof plywood and steel prop formwork for all concrete works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett for foundation/Column/Sill/Lintel/Slab/Beam etc including cost of all materials, all complete as per specification, drawings and as per instruction of engineer.	SQM	17.01				
7	Reinforcement Steel Works: Providing, straightening, cleaning, cutting, fabricating, bending, stirrups making and tying TMT (Fe 500) for main reinforcement bars and binding the bars with 18 gauge annealed wire for tying them at each junction as per design and details for all types of RCC elements including all waste and cut pieces, provision for spacers, chairs, providing and placing cover blocks cement mortar (1:1) to keep the bars in the intended position at all levels etc. including cost of all materials and accessories, all complete as per specification, drawings and instruction of engineer	KG	90.57				
8	Providing & laying with approved quality local chimney made first class bricks for super and substructure in 1:4 cement(OPC 43 grade Minimum) sand mortar finished in perfect line & level including wetting the bricks, packing the joints & curing the work all complete as per drawings, specification & Instruction of Site Engineer.	CUM	12.97				
9	Supplying and laying 38mm thick PCC in Flooring in the ratio of 1:2:4 with approved quality of OPC cement sand and 12 mm down aggregates including 1:1 C/S punning all complete as per specification, drawings and as per Instruction of Site Engineer Engineer.	SQM	28.57				
10	Fixing of existing Seasoned Sal Wood Frame (75mmx100mm) for Door/Window/ Ventilation including one coat of Primer and two coat of Emamel Painting with all hardware item (Holdfast etc )and all complete works per specification as per Instruction of Site Engineer.	CUM	3.71				
11	Supply and fitting of an aluminium door fitted in a wooden door frame as per the instructions of the engineers.	SQM	2.06				
12	Supplying and Plastering with 12.5 mm plaster in walls in 1:4 cement sand plaster in walls in perfect line and level using approved quality of OPC cement and sand include curing and and all complete as per specification, drawings and Instruction of Site Engineer	SQM	94.40				

  
 बाबुरबाबा नगरपालिका  
 नगर कार्यपालिकाको कार्यालय  
 बुधवार, बर्दिया  
 सुनसरी प्रदेश नेपाल  
 स.स. २०७३

माल बहादुर शाही  
मुख प्रशासक अधिकृत

BOQ						
Description	Unit	Quantity	Rate (Rs)		Amount ( NRs)	Remarks
			In Figure	In Words		
13 Providing and fixing of 26 guage (0.37 mm) Coloured corrugated CGI sheet (meadium class) for roof including fixing in proper shape and size with all necessary rails screws bolts and nuts washer J & L hooks etc including cost of materials and accessories etc all complete as per specification, drawings & Instruction of Site Engineer.	SQM	49.98				
14 Providing and fixing of 26 guage (0.37mm) colour GI sheet (medium class) for roof ridge of width 60 cm including fixing in proper shape and size with all necessary rails screws bolts and nuts washer J & L hooks etc including cost of materials and accessories etc all complete as per specification, drawings & instruction of Site Engineer	RM	29.92				
15 Providing and fixing of Bambo Frame and Thatch for roof in proper shape and size including with all necessary materials and accessories all complete as per Instruction of Site Engineer.	SQM	49.98				
16 Fixing of existing Seasoned Sal Wood (38mmx75mm) for making a mirror frame including 6mm Plain White Glass for Window and Door with all hardware item (chiskini,handle,hinge etc) and all compete works per specification as per Instruction of Site Engineer.	SQM	10.08				
<b>Total Construction Cost (B)</b>						
<b>VAT(13%)</b>						
<b>General Cost (A)</b>					3000.00	
<b>GRAND TOTAL COST</b>						
<b>Total Amount In Words :</b>						
Name of Firm :						
Address of Firm :						
Authorized Signature :						
Designation :						
Date :						

सुनसरी नगरपालिका  
नगर कार्यपालिकाको कार्यालय  
सिन्धुवार, बाँदैया  
सुनसरी प्रदेश नेपाल  
स्था. २०७३