



नगर कार्यपालिकाको कार्यालय

Office of the Municipal Executive



(Google Plus Code: C8RJ+C6 Neulapur)

सैनवार, बर्दिया
Sainawar, Bardiya

लुम्बिनी प्रदेश, नेपाल
Lumbini Province, Nepal

विषय: दरभाउपत्र पेश गर्ने सम्बन्धि सार्वजनिक सूचना ।
(सूचना प्रकासन मिति: २०८०/१२/१५)

प्रस्तुत विषयमा यस कार्यालयबाट तत्काल ठाकुरद्वारा— हात्तिसार कालोपत्रे सडक निर्माणमा सिभिल इन्जिनियरिंग परामर्श सेवा खरिद गर्नुपर्ने भएकोले यस पत्रसाथ सम्लग्न TOR र BOQ बमोजिमको काम के कति दररेटमा गर्न सकिने हो ७ दिन भित्र दरभाउपत्र तपसिल बमोजिमको कागजातसहित पेश गर्नु हुन जानकारी गराइन्छ ।

तपसिल:

- १) व्यवसाय दर्ता प्रतिलिपि
- २) स्थाई लेखा नम्बर दर्ता प्रमाणको प्रतिलिपि
- ३) अ. बा २०७९/८० को कर चुत्ता प्रमाणपत्रको प्रतिलिपि
- ४) नगरपालिकामा स्कृति भएको प्रमाण पत्र वा स्कृति हुनलाई निवेदन
- ५) नेपाल इन्जिनियरिंग परिषदद्वारा जारी गरिएको सिभिल इन्जिनियरिंग लाइसेन्स
- ६) कम्तिमा पाँच वर्षा सिभिल इन्जिनियर भाई कालोपत्रे सडक निर्माण संग सम्बन्धित अनुभवपत्र

२०८०/१२/१५
रामहरि रिजाल
प्रमुख प्रशासकीय अधिकृत

THAKURBABA MUNICIPALITY
OFFICE OF MUNICIPAL EXECUTIVE
SAINWAR, BARDIYA

Terms of Reference (TOR)

For

Hiring of Civil Engineering Consultancy Service in Thakurdwara Hatisar Black Top Road
Construction Contract No: TBM/W/NCB-12/080/81

Thakurbaba Municipality
sainwar, Bardiya
Fiscal Year 2080/81

**Terms Of Reference (ToR) For Hiring of Civil Engineering
Consultancy Service in Thakurdwara Hatisar Black top Road
Construction Contract No:- TBM/W/NCB-12/080/81**



1. Background

Project is located in Thakurbaba Municipality, Ward No 9, Thakurdwara. The project includes construction of Premix Black Top Road of length 2.2 Km which starts from Tharu chowk to Banu gau. The estimated cost of this project is Rs. 29322523.2 and final bidding price is Rs. 24103408.32 which should be completed within this fiscal year. Due to technical difficulties and shortage of road expert, office is seeking for experienced consultants for overall supervision and implementation of the project.

2. Objective

The primary objective for hiring this service is to provide expert guidance, technical oversight, and project management support for the construction of a Thakurdwara Hatisar Black Top Road Construction Contract No (TBM/W/NCB-12/080/81).

The consultant's responsibilities will include, but not be limited to:

3.1. Construction Phase

- Study the Design, Drawing, Specification and BOQ of this Project.
- Joint survey, supervision and monitoring the construction activities to ensure compliance with approved plans, design and specifications and quality.
- Any Written direction, instruction to contractor regarding Quality as per Contract Document.

4. Deliverables

The consultant is expected to deliver the following:

- Joint Survey Report and Design
- Contractors Bill along with Drawing for Approval
- Approval of As Build Drawing proposed by contractor.

5. Timeline

The expected duration of consulting service should be until the completion of the project. The consultant must be available during the major activity like subbase, base and premix carpet.

डॉ. बानु प्रसाद थारु
NEC १८५२९/सिगिल 'क' वर्ग

रामहरि रिजाल
प्रमुख प्रशासकीय अधिकृत

6. Qualifications

Bill of Quantities

General Bidding Information			
JV Name	Bidder Email	IFB No	Submitted on
ROYAL-LAXMIPUJA-OM NAMA JV	purnaraj2076@gmail.com	TBM/W/NCB-12/080/81	12/28/2023 11:08:33 AM

1 Provisional Sum

Procurement Item Details

Sl. No.	Item Description	Unit	Quantity	Rate(NRs)	Rate in Words	Amount(NRs)
1	Supply and erection of Project Information board 1.8 x 1.2 m size including full compensation for labour, materials, transportation and other incidental all complete as per Instruction of site Engineer.	PS	1.0	3,000.00	three thousand	3,000.00
2	Provision for carrying out additional tests (Extra Test which in force of Site Engineer) for material and works as required and instructed by the Engineer as per GCC	PS	1.0	10,000.00	ten thousand	10,000.00
3	Insurance premium for the work, plant and materials, damage for contract work for all risk including Riot, Strike, Damage, Malicious damage and Terrorism. Named and un Named Personnel, Equipment, Third. Party for construction period+ 1 Year (SCC 19.1)	PS	1.0	50,000.00	fifty thousand	50,000.00
4	Provide and Maintenance Traffic safety, control measures and temporary diversions during construction as instruction by the Engineer	PS	1.0	5,000.00	five thousand	5,000.00
5	Costs for other miscellaneous items as per site requirement & as per Instruction of Site Engineer.	PS	1.0	100,000.00	one hundred thousand	100,000.00
Total						168,000.00

2 Construction work

2.1 Road Construction Work

Procurement Item Details

Sl. No.	Item Description	Unit	Quantity	Rate(NRs)	Rate in Words	Amount(NRs)
1	Relocation of electricity poles including necessary accessories (D-iron, Stay wire, transmission wire, Electricity shut down charge and all) as per instructed by Site Engineer.	Nos	29.0	15,000.00	fifteen thousand	435,000.00
2	Road way Excavation in all types of soil By Mechanical Means as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and	Cum	330.0	100.00	one hundred	33,000.00

[Signature]

गुण बहादुर थारु
NEC १८४२९ "सिमिल" क वर्ग

रामेश्वर रिजाल
प्रमुख प्रशासकीय अधिकृत



रमिहरी रिजाल
मुख्य प्रशासकीय अधिकृत

Item Details		Quantity	Rate (₹)
1. Cement		100	1000
2. Sand		200	2000
3. Aggregate		150	1500
4. Labour		50	500
5. Transport		10	100
6. Water		5	50
7. Electricity		2	20
8. Miscellaneous		1	10
Total		518	5180

John

रामहरि रिजाल
प्रमुख प्रशासकीय अधिकृत

Procurement Item Details

Sl. No.	Item Description	Unit	Quantity	Rate(NRs)	Rate in Words	Amount(NRs)
18	premix carpet composed of 13.2 mm to 5.6 mm aggregates as wearing course on a previously prepared base as per drawing and Technical Specification and as per instruction of site Engineer.(SS/SP-1311)	Cum	411.95	16,000.00	sixteen thousand	6,591,200.20
19	Providing and laying seal coat sealing (using crushed stone chipping/washed sand) the voids in a bituminous surface as per Drawing, Technical Specifications and as per instruction of site Engineer.(SS/SP 1310)	Sqm	11770.0	60.00	sixty	706,200.00
20	Road Marking with Hot Applied Thermoplastic Compound with Reflectorizing Glass Beads on Bituminous Surface On smooth surface (similar to Asphalt concrete and rigid pavement) as per instruction of Engineer.(SS/SP 1503)	Sqm	535.0	800.00	eight hundred	428,000.00
21	Providing and installation of 150mmx150mmx1.5m long delineators (roadway indicators, hazard markers, object markers), 80-100cm high above ground level, painted black and white in 20cm wide strips, buried or pressed into the ground and conforming to the drawings and Technical Specifications and as per instruction of site Engineer.(SS/SP 1507)	Nos	30.0	2,000.00	two thousand	60,000.00
Total						21,181,777.41

Total of Procurement Items

Total Item Price	21,181,777.41
VAT	2,753,631.06
VAT %	13.0
Grand Total	24103408.01

[Signature]

[Signature]
इ. बीन बहादुर थारु
NEC १८५२९ "सिभिल" क' वर

[Signature]
रामहरि रिजाल
प्रमुख प्रशासकीय अधिकृत



Thakur Baba Municipality
Office of the Municipal Executive
Sainawar Bardiya

Bill of Quantity

Project Name :- Hiring Civil Engineering Consultancy Service For Construction Of Thakurdwara-Hattisar Black Top Road Construction

Location:- Thakurbaba Municipality, Bardiya

Types Of Work:- Consulting Work

SN.	Description of Works	Unit	Quantity	Rate(Rs)		F/Y	2080/81
				Rate in figure	Rate in Words	Bajet Sub-head	
						Amount (NRs)	Remarks
1	Hiring of civil engineering consultancy service for supervision of project (includes surveying, quality control, drawing, bills and transportation, accomodation, miscellaneous cost) as per TOR and Instruction Of Engineer.	JOB	1				
					Total Without Vat		
					Vat 13%		
					Grand Total		

इ. बाल बहादुर थारु
NEC १८५२९ सिविल क वर्ग

रामहरि रिजाल
प्रमुख प्रशासकीय अधिकृत