



नगर कार्यपालिकाको कार्यालय



Office of the Municipal Executive

(Google Plus Code: C8RJ+C6 Neulapur)

सैनवार, बर्दिया
Sainawar, Bardiya

लुम्बिनी प्रदेश, नेपाल
Lumbini Province, Nepal

प.सं. ०७९/८०

मिति: २०७९/१२/२२

सुचना सुचना सुचना ।

प्रस्तुत बिषयमा ठाकुरबाबा नगरपालिका वडा नं ४ मा स्थित मैनवार खोपकेन्द्र व्यावस्थापनको लागि Electrical . Grill work र अन्य मर्मत सम्भार कार्यको लागि निम्न बोमोजिम BOQ मा के कति दर भाउमा गर्न सकिने हो तपसिल कागज सहित मिति २०७९/१२/२६ गते भित्रमा कार्यलयमा पेस गर्नु हुन नगरपालिकामा सुचिकृत भएका सबै संस्थाहरुलाई यसै सुचना बाट जानकारी गराइन्छ ।

Handwritten signature and date: 21/12/22

तपसिल

संस्था दर्ता प्रतिलिपि ।

आ.ब २०७९/८० को लागि संस्था नविकरण भएको प्रमाण पत्रको प्रतिलिपि ।

स्थायि लेखा नम्बर दर्ता प्रमाणको प्रतिलिपि ।

आ.ब २०७८/७९ को कर चुक्ताको प्रतिलिपि ।

नगरपालिका संस्थाको सुचिकृत सम्बन्धि प्रमाणपत्र वा व्यवसाय दर्ता प्रमाणको प्रतिलिपि ।

दररेट सहितको BOQ

प्रमुख प्रशासकीय अधिकृत
रामहरि रिजाल
प्रमुख प्रशासकीय अधिकृत

BOQ

Date:-

सुचिबानी प्रदेस, (संसार: २०७७)

F/Y: 2079/080

71
रामहरि रिजाल
प्रमुख प्रशासकीय अधिकृत

Thakurbaba Municipality
Office of Municipal Executive
Sainawar Bardiya

BOQ

Project Name :- Mainawar khopkendra ko byabasthapan


Location :- Thakurbaba-4

Type of Work :- Electrical & Grill work

Date:-

F/V: 2079/080

SN.	Description	Unit	Quantity	Rate In Figure(NRS)	Rate In Words	Amount	Remarks
7	Supplying and Plastering with 12.5 mm plaster in walls in 1:4 cement sand plaster in walls in perfect line and level using approved quality of OPC cement and sand include curing and all works complete and as per the instruction of the site Engineer.	sqm	20.28				
8	Providing and applying one coat of primer on all exterior plastered/ wall putty surface of wall, column, beam and ceiling of the buildings-including cleaning and wetting the surface with cost of all materials and accessories, all complete as per specification ,drawings and as per Instruction of Site Engineer (Asian paint/ Jenson & Nicolson or equivalent).	sqm	20.28				
9	Supplying and fixing Diffrent Size MS square Pipe For Railing Work Include one coat primer and Two Coat Paint all complete.	kgs	67.27				
10	Supplying and fixing MS window using different size solid core MS grill in metal frame includes brushing with sand paper applying one coat primer,two coat enamel/aluminium paint/reodoxide as per instruction of Site Engineer.	Kgs	184.68				
11	Supply of materials and wiring with PVC Insulated copper wire in NS Approved HDP conduit without any joint in middle of the span with necessary connecting, fixing, insulating and jointing materials as per drawing and specification complete (wire: Trishakti, Pioneer, Limus) a) Light/ Fan Points Light and Fan point with 3/22 NS Approved wire, bends, circular & Junction boxes as per instruction of site engineer.	Points	10.00				
12	Supply of materials and wiring with PVC Insulated copper wire in NS Approved HDP conduit without any joint in middle of the span with necessary connecting, fixing, insulating and jointing materials as per drawing and specification complete (wire: Trishakti, Pioneer, Limus) b) Power point 15 A with 3/22 or 7/22 NS approved wire, bends, circular & Junction boxes as per instruction of site engineer.	Points	4.00				



Signature

रामहरि रिजाल
प्रमुख प्रशासकीय अधिकृत

Thakurbaba Municipality
Office of Municipal Executive
Sainawar Bardiya

BOQ

Date:-

Project Name :- Mainawar khopkendra ko byabasthapan

Location :- Thakurbaba-4

Type of Work :- Electrical & Grill work

F/Y: 2079/080

SN.	Description	Unit	Quantity	Rate In Figure(NRs)	Rate In Words	Amount	Remarks
13	Supply and fixing of 16 Amp main switch as per instruction of site engineer.	Nos	4.00				
14	Supply and installation of 12 watt LED bulb (standard, rodex, Geco, havells) & other equivalent company all complete as per instruction of site engineer.	Nos	6.00				
15	Supply and installation of ceiling 48"fan (standard, rodex, Geco, havells, crompton, usha) & other equivalent company all complete per instruction of engineer.	Nos	4.00				
16	Supply and installation of NEA Electrical Meter Box with All Coplete Set.	Nos	1.00				
			Total				
				Vat(13%)			
				Total Amount			



Total Amount In Words:-

Name Of Form:-

Address Of Form:-

Proprienter:-

Sinnature and Stamp

(Signature)

(Signature)
रामहरि रिजाल
प्रमुख प्रशासकीय अधिकृत