



नगर कार्यपालिकाको कार्यालय

Office of the Municipal Executive

(Google Plus Code: C8RJ+C6 Neulapur)

सैनवार, बर्दिया
Sainawar, Bardiya

लुम्बिनी प्रदेश, नेपाल
Lumbini Province, Nepal


दरभाउपत्र (कोटेशन) पेश गर्ने सम्बन्धी सूचना ।

(सूचना प्रकाशन मिति २०८१/०७/०४, ने.सं. ११४४ कौलागा: ३, आइतबार)

यस ठाकुरबाबा नगरपालिकाको “Krishna mandir Toilet finishing work” योजना कार्यन्वयन गर्नुपर्ने भएकोले इच्छुक निर्माण कम्पनी / फर्मले यो सूचना प्रकाशन भएको मितिले २०८१/०७/०९ गतेको कार्यालय समय भित्र आवश्यक कागजात सहित संलग्न ढाँचामा दरभाउपत्र (कोटेशन) पेश गर्नुहुन सम्बन्धित सबैको जानकारीका लागि यो सूचना प्रकाशित गरिएको छ ।

संलग्न गर्नुपर्ने आवश्यक कागजातहरू:

१. व्यवसाय दर्ता / इजाजत पत्रको प्रतिलिपी
२. स्थायी लेखा (प्यान/भ्याट) दर्ता प्रमाणपत्रको प्रतिलिपी
३. कर चुक्ता प्रमाणपत्रको प्रतिलिपि (आ.व. २०८०/०८१ वा म्याद थप)
४. ठाकुरबाबा नगरपालिकामा सूचिकृत भएको प्रमाण वा निवेदन
५. ठाकुरबाबा नगरपालिकाको राजश्व शाखामा रु. १०००/- तिरेको रसिदको प्रतिलिपी


नारायण प्रसाद ठकुर
प्रमुख प्रशासकीय अधिकृत

"समुन्नत ठाकुरबाबा: सबल नगरवासी"

वेबसाइट: www.thakurbabamun.gov.np ईमेल: thakurbabamun@gmail.com

Bill of Quantities

General Bid Info



Bidder Name

Bidder Email

Project Name

Submitted on

1 Provisional Sum

Procurement Item Details

Sl. No.	Item Description	Unit	Quantity	Rate(NRs)	Rate in Words	Amount(NRs)
1	Costs for other miscellaneous items as per site requirement & as per Instruction of Site Engineer.	1	1.0	20,000.00	Twenty thousands	20,000.00
Total						20,000.00

2 Construction work

Procurement Item Details

Sl. No.	Item Description	Unit	Quantity	Rate(NRs)	Rate in Words	Amount(NRs)
1	Earthwork excavation in all Soft/Medium soils for building foundation and site development by Manually, lift up to 1.5m ramming of bottom , stacking of excavated materials at 10m, clear from the edge of foundation trench, all complete as per specification, drawings and instruction of site engineer	Cum	1.25			
2	Providing and laying of hand packStone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications and Instruction of Site Engineer.	Cum	0.38			
3	Providing, laying, compacting and curing plain cement concrete M15 (1:2:4) with OPC cement 43 grade Minimum, crusher washed sand and crushed aggregate(using mixture machine) finishing to approved level, lines and dimensions using vibrator and all complete as per drawings, specifications and as per Instruction of Site Engineer.	Cum	2.66			



Procurement Item Details							
Sl. No.	Item Description	Unit	Quantity	Rate(NRs)	Rate in Words	Amount(NRs)	
4	Formworks: Providing 12mm thick waterproof plywood and steel prop formwork for all concrete works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett for foundation/Column/Sill/Lintel/Slab/Beam etc including cost of all materials, all complete as per specification, drawings and as per instruction of engineer.	Sqm	3.59				
5	Providing & laying with approved quality local chimney made first class bricks for super and substructure in 1:4 cement(OPC 43 grade Minimum) sand mortar finished in perfect line & level including wetting the bricks, packing the joints & curing the work all complete as per drawings, specification & Instruction of Site Engineer.	Cum	2.70				
6	Supplying and laying 38mm thick PCC in Flooring in the ratio of 1:2:4 with approved quality of OPC cement sand and 12 mm down aggregates including 1:1 C/S punning all works complete as per Instruction of Site Engineer.	Sqm	9.03				
7	Supplying and Plastering with 12.5 mm plaster in walls in 1:4 cement sand plaster in walls in perfect line and level using approved quality of OPC cement and sand include curing and all works complete and as per the instruction of the site Engineer.	Sqm	5.27				
8	(Potico stainless steel pipe ralling) Supply and fixing of stainless steel pipe ralling with 2" dia. Hand rail pipe,vertical 1.5" dia. Pipe every 5' distance with 39" height and 3/4" dia. Pipe 4 line horizontal line and all complete work.	Rm	8.30				
9	Providing and Laying Reinforced cement concrete of 900 mm Internal Dia. NP3 Flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications and as per instruction of engineer.(SS/SP 701)	Rm	5.00				



Procurement Item Details

Sl. No.	Item Description	Unit	Quantity	Rate(NRs)	Rate in Words	Amount(NRs)
10	Back Filling behind abutment, wing wall and retaining wall with excavated earth material with proper compaction in every 15cm depth as per drawing Technical Specifications and instruction of engineer.(SS/SP 908)	CUM	19.00			
11	Supply and fixing of 1000 Ltr. PVC\HDPE Water Tank including all assories and fitting as per the instruction of site engineer.	Job	1.00			
					Total	
Total of Procurement Items						
Total Item Price						
VAT						
VAT %						
Grand Total						

Name of Company :

Authorized Signature :

Name of Authorised Person :

Company Stamp :