

स्थायी लेखा नं.: २०१२९६१९०
कार्यालय कोड नं.: ८०१०५१२८

ठाकुरबाबा नगरपालिका
Thakurbaba Municipality



नगर कार्यपालिकाको कार्यालय



Office of the Municipal Executive

(Google Plus Code: C8RJ+C6 Neulapur)

सैनवार, बर्दिया
Sainawar, Bardiya

लुम्बिनी प्रदेश, नेपाल
Lumbini Province, Nepal

विषय: दरभाउपत्र पेश गर्ने सम्बन्धि सार्वजनिक सूचना ।

(सूचना प्रकासन मिति: २०८३/०२/२०)

प्रस्तुत विषयमा यस कार्यालयबाट वडा न. ०४ मा बगनाहा स्वास्थ्य चौकी र कृषि सेवा केन्द्रको बाटो ढलान निर्माण कार्य सम्पन्न गर्नुपर्ने भएकोले उक्त कार्यको स्वीकृत लागत अनुमान रु.२७९,३२०।०६ (मु.अ.कर सहित) भित्र रही कार्यालयबाट उपलब्ध गराइएको BOQ तथा Specification बमोजिम उक्त निर्माण कार्य गर्न ईच्छुक निर्माण ब्यवसायी तथा फर्महरुबाट यो सूचना प्रकाशित भएको मिति देखि २ दिन भित्र (मिति २०८३/०२/२२) भित्र के/कति दरमा गर्न सकिने हो? दरभाउपत्र र तपसिल बमोजिमको कागजातसहित पेश गर्नु हुन जानकारी गराइन्छ।

तपसिल:

- १) व्यवसाय दर्ता प्रतिलिपि •
- २) स्थाई लेखा नम्बर दर्ता प्रमाणको प्रतिलिपि
- ३) आ. बा २०८१/८२ को कर चुत्ता प्रमाणपत्रको प्रतिलिपि

मंगल बहादुर शाही
प्रमुख प्रशासकीय अधिकृत

"समुन्नत ठाकुरबाबा: सबल नगरवासी"

वेबसाइट: www.thakurbabamun.gov.np ईमेल: thakurbabamun@gmail.com


मंगल बहादुर शाही
 प्रमुख प्रशासकीय अधिकारी
 थकुरबाबा नगरपालिका कार्यालय
 सैनवार बर्दिया
 कैलाल प्रदेश नेपाल
 स्था.सं. १७७३

Thakurbaba Municipality
 Office of Municipal Executive
 Sainawar Bardiya

Project Name :- Swathya chauki Tatha & Sewa KendraKo Bato Dhalan
 Location :- Thakurbaba Municipality-04
 Type of Work :- RCC & PCC Road Construction
 Estimated Work Completion Date :

F.Y.: 2082/83

BOQ							
SN.	Description	Unit	Quantity	Rate (Rs)		Amount (NRs)	Remarks
				In Figure	In Words		
1	Surface dressing, ,cutting undulated area,filling pot holes,leveling and all complete all complete as per specification, drawings and instruction of site engineer.	SQM	94.42				
2	Earthwork excavation in all Soft/Medium soils for building foundation and site development by Manually, lift up to 1.5m ramming of bottom , stacking of excavated materials at 10m, clear from the edge of foundation trench, all complete as per specification, drawings and instruction of site engineer.	CUM	5.26				
3	Providing, laying, compacting and curing plain cement concrete M15 (1:2:4) with OPC cement 43 grade Minimum, crusher washed sand and crushed aggregate(using mixture machine) finishing to approved level, lines and dimensions using vibrator and all complete as per drawings, specifications and as per Instruction of Site Engineer.	CUM	18.66				
4	fabricating, bending, stirrups making and tying TMT (Fe 500) for main reinforcement bars and binding the bars with 18 gauge annealed wire for tying them at each junction as per design and details for all types of RCC elements including all waste and cut pieces, provision for spacers, chairs, providing and placing cover blocks cement mortar (1:1) to keep the bars in the intended position at all levels etc. including cost of all materials and accessories, all	KG	324.75				
5	Formworks: Providing 12mm thick waterproof plywood and steel prop formwork for all concrete works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett for foundation/Column/Sill/Lintel/Slab/B eam etc including cost of all materials, all complete as per specification, drawings and as per instruction of engineer.	SQM	11.86				



गंगुल बहादुर शाही
प्रशासकीय अधिकृत

BOQ

Description	Unit	Quantity	Rate (Rs)		Amount (NRs)	Remarks
			In Figure	In Words		
6 Laying Of Dry Brick Flooring in perfect line and level with Sand including Ground Compaction and the cost of all materials and other accessories etc all complete as per specification, drawings and Instruction of Site Engineer	SQM	186.65				
SUB-TOTAL						
VAT(13%)						
GRAND TOTAL						

Total Amount In Words:

Name of Firm:

Address of Firm:

Authorized Signature:

Designation:

Date: